CHITALDRUG DIVISION.

Dated 22nd July 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 15th August 1904, for restoring Andanur tank Registered No. 186 of Holalkere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1906.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 80 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Andanur tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

List showing the quantities of work to be done under each item for restoring the Andanur Tank, Registered No. 186, Holalkere Taluk.

Items of work.	*Per.*	*quantity.*
Bund 56·00 and top width 6 feet—		
Earthwork to bund, watering and tamping, etc., from foundations ...	C. yd.	1,816
Do do from pits in bed ...	,,	2,526
Earthwork excavation and re-filling foundations	,,	1,483
Do do to be left as spoil bank ...	,,	1,288
Puddle wall with a mixture of ⅔ gravel and ⅓ red earth, watering and tamping.	,,	1,417
Turfing	S. yds.	6,690
New grade stones	No.	12
Removing and re-fixing old grade stones	,,	40
New B. M. stones	,,	2
Gauge stones	,,	1
Top width stones	,,	52
Registered number stones	,,	1
Year stone	,,	1
Clearing jungle	Lump sum.	Rs.
Earthwork foundation to raise revetment	C. yd.	248
Dismantling and re-building old stone work	,,	1,400
New stone work	,,	3,003
Gravel backing with ⅓ red earth and ⅔ gravel, lead under ¼ mile, watering and tamping.	,,	2,687
Right waste weir 75 feet long and R. L. 50·00—		
Earthwork excavation	C. yd.	1,142
Burnt brick in surki mortar	C. ft.	597
Burnt stone slabs	S. ft.	323
Rough plastering	Sqr.	5·70
Nice do	,,	1·95
Rough stone work	C. yd.	168
Cutting joints of slabs	Lump sum.	
Repairing the present waste weir 100' long—		
Old stone work	C. yd.	200
Plastering the body wall, etc.	Lump sum	Rs.
Sluice No. 1—		
Cut opening and repairing the sluice	Lump sum	Rs.

Y. SRINIVASA RAO, *Executive Engineer.*